

**CORRIGENDUM**

**(A copy to be enclosed with sign and seal of the tenderer along with the technical bid)**

**TWO PART OPEN TENDER TOWARDS THE BUILDING ELECTRICAL WIRING WORK AT SMP GODOWN AND GENERAL STORES, DAIRY CUM POWDER PLANT, THIRUVANNAMALAI**

The following amendments are hereby made in the tender documents towards the building electrical wiring work at SMP Godown and General Stores, Dairy cum Powder Plant, Thiruvannamalai:

As per tender document, the quantity mentioned in the technical bid (Page No.52) are furnished below:

Note: Quantity can be increase/decreased as per requirement.

Particulars	Quantity		Total
	SMP SV	GS	
1. Supply, installation, Testing and Commissioning of 4 feet 18/20 watt LED Tube light	24	64	88
2. Supply, installation, Testing and Commissioning of 70 watt LED light	8	12	20
3. Supply, installation, Testing and Commissioning of Main LDB Panel	1	1	2
4. Supply, installation, Testing and Commissioning of 4 feet 18 watt LED Emergency light	2	4	6
5. Supply, installation, Testing and Commissioning of Lighting DBs	4	8	12
6. Supply, installation, Testing and Commissioning of chemical Earthing	2	4	6
7. Supply, installation, Testing and Commissioning of Power points for Exhaust Fan and Power sockets	4	8	12
8. Supply and laying of Power Cables 3.5 Core X 70 Sq mm aluminium armored cable as per drawing	250 RM		250 RM
9. Laying of 3 Core X 2.5 Sq.mm Copper armored cable.	250 RM		250 RM
10. Supply and laying of Primary & Secondary wiring with switch Point and wiring accessories and raw power points (3 Run X 2.5 Sq. mm). Laying of Conduit pipe along with wiring conduit pipe of MS type.	1600 RM		1600 RM

On the above, the quantity mentioned in the technical bid(Page No.52) may be read as follows:

Note: Quantity can be increase/decreased as per requirement.

Particulars	Quantity		Total
	SMP SV	GS	
1. Supply, installation, Testing and Commissioning of 4 feet 18/20 watt LED Tube light fittings read as twin fittings	24	64	88
2. Supply, installation, Testing and Commissioning of 70 watt LED light with junction box connectors.	8	12	20
3. Supply, installation, Testing and Commissioning of Main LDB Panel with locking double doors. Incoming - 100 A, MCCB, 4 pole Outgoing – 63A X 2nos., MCB, 4 pole Outgoing – 32A X 2nos., MCB, 4 pole	1	1	2
4. Supply, installation, Testing and Commissioning of 4 feet 18 watt LED Emergency light	2	4	6
5. Supply, installation, Testing and Commissioning of Lighting DBs with locking double doors. Incoming - 63 A, RCBO, 4 pole, 30 mA. Outgoing – 32A X 3nos., ELCB, 2 pole, 30 mA Outgoing – 6A to 16A MCB, Single pole, each 8 segment MCB.	4	8	12
6. Supply, installation, Testing and Commissioning of chemical Earthling	2	4	6
6(a). Supply and laying of GI flat	50 RM	100 RM	150 RM
7. Supply, installation, Testing and Commissioning of Power points for Exhaust Fan and Power sockets	4	8	12
7(a). Supply and laying of copper wire of 3 Run X 4 Sq. mm	200 RM	300 RM	500 RM
8. Supply and laying of Power Cables 3.5 Core X 70 Sq mm aluminium armored cable as per drawing	250 RM		250 RM
8(a). Supply and installation of end termination	4 Nos.		4 Nos.
9. Supply and Laying of 3 Core X 2.5 Sq.mm copper armored cable.	250 RM		250 RM
9(a). Supply and installation of end termination	12 Nos.		12 Nos.
10. Supply and laying of Primary & Secondary wiring with switch Point and wiring accessories and raw power points ( 3 Run X 2.5 Sq. mm). Laying of wiring conduit pipe of MS type with MCB controls.	1600 RM		1600 RM

**For Joint Managing Director.**