

## **CORRIGENDUM**

### **(Authenticated copy of the corrigendum to be enclosed along with Part-I Technical bid)**

#### **Two Part Open Tender for the supply, erection and commissioning of 2 Sets of Anti Cold Room Refrigeration Unit of Capacity 5 TR to Products Dairy**

The following amendments are hereby made in the tender documents for the supply, erection and commissioning of 2 Sets of Anti Cold Room Refrigeration Unit of Capacity 5 TR to Products Dairy:

#### **Technical Bid**

1. As per tender document, Technical Specification(Page no.27, Sl. No.4) of technical bid is as follows:

4. Temperature Range : 0°C to 4°C

Technical Specification(Page no.27, Sl. No.4) of technical bid may be read as follows:

4. Temperature Range : 2°C to 4°C

2. As per tender document, Technical Specification(Page no.27, Sl. No.10) of technical bid is as follows:

10. Piping & Drain Lines: Necessary piping with hardened copper(NIPPON Make) with proper insulation & drain line arrangement using ashirwad UPVC pipes of 2" diameter to be used.

Technical Specification(Page no.27, Sl. No.4) of technical bid may be read as follows:

10. Piping & Drain Lines: Approximate copper piping of 50 feet length for both sets with Hardened Copper(NIPPON Make) with proper insulation & drain line arrangement using ashirwad UPVC pipes of 2" diameter to be used.

3. As per tender document, Technical Specification(Page no.27, Sl. No.11) of technical bid is as follows:

11. Electrical Wiring: Necessary input power shall be arranged near the condensing units & required control wiring & all other Cabling shall be in the suppliers scope. Wires/Cables, FINOLEX/ ORBIT/POLYCAB/HAVELS make only to be Used with proper insulations.

Technical Specification(Page no.27, Sl. No.11) of technical bid may be read as follows:

11. Electrical Wiring: Necessary input power shall be arranged near the condensing units & required control wiring & all other Cabling shall be in the suppliers scope.

Wires/Cables - FINOLEX/ORBIT/POLYCAB/HAVELS make only to be used with proper insulations.

Approximate input cable length may be 60 metres from Main Panel to Control Panel.

4. The following additions may be included in the tender document on Technical Specification(Page no.27) of technical bid is detailed below:

The room size : Length 30 feet x Width 8 feet x Height 9 feet.

SCOPE OF WORK(in respect of supplier):

1. Unpacking, shifting, positioning of two complete sets of Cold Room Refrigeration Unit of capacity 5 TR for Product Dairy, Chennai – 98 for Kulfi Mix Storage.
2. Commissioning of the equipment, trial operation for assessing the performance, a continuous trial for 24 hours with 100% capacity for 15 days will be conducted.
3. All types of mechanical works in the installation of machine are under the supplier's scope.
4. Compressor warranty : 2 years.
5. All safety measures and safety guard for compressor(outdoor units).
6. Outdoor units is of IP 65.

**Joint Managing Director.**